

ProSource Prefabricated Containment Systems

Strong, Versatile, Quick to Install

Flat-pack, prefabricated cold & hot aisle containment systems keep costs down and dramatically reduce installation time. We are changing the way containment is deployed in new data center construction, providing relief for both construction schedules and budgets. Our prefabricated, flat-pack containment system is a smarter way to build because it installs in half the time of traditional stick-built systems and costs about a third less. Because containment is typically the final phase of data center construction, faster containment installation can mean finishing on time. Building containment in our factory instead of on your site reduces cost and improves quality. We offer both Polargy PolarPlex Containment Systems and Tate Airflow ContainAire Containment Systems.



High Tech Design, Low Tech Assembly

We provide containment systems that assemble easily onsite, giving architects and builders a fast and cost effective way to build the containment system. The upper tier is an expanding cube architecture that ships flat, opens to form the containment plenum, is lifted into place, and attached to the ceiling. The lower tier integrates Polargy's patent pending Suspended Panel System for filling empty rack spaces or for completely isolating the aisle for commissioning. These filler panels simply "hook onto" the upper tier. Polargy's popular auto-close P2 Sliding Doors or Swing Doors or used for closing the aisle ends.

ProSource is an approved Polargy and Tate Containment Partner

Polargy and Tate are leading providers of hot aisle and cold aisle containment solutions for new data center construction and retrofit projects. Let us assist with design and installation of a complete turnkey containment solution for your data center.

The right choice for protecting data center assets